

# EPSOM PLAYHOUSE HANGING PLOT

PRODUCTION :

DATE :

BAR	HANG	DISTANCE FROM PROS (m)	DISTANCE FROM STAGE EDGE (m)
22	Cyc - permanent	7.60	8.92
21		7.40	8.72
20		7.20	8.52
W 7	Cyc LX	6.90	8.22
19		6.60	7.92
18		6.40	7.72
17		6.20	7.52
16a	LX4 (hand winch)	6.03	7.35
16		5.80	6.12
15		5.60	6.92
14		5.38	6.70
13		5.15	6.47
W 6	LX3	4.93	6.25
12		4.63	5.95
11	Black Tabs - permanent	4.25	5.57
10a	Border - permanent	4.20	5.52
10		3.98	5.30
9		3.63	4.95
8		3.43	4.75
W 5	LX2	3.18	4.50
7		2.85	4.17
6		2.68	4.00
5		2.48	3.80
4		2.27	3.59
3		2.07	3.39
2	Cinema screen - permanent	1.87	3.19
W 4	LX1	1.62	2.94
1		1.32	2.64
0	House border - permanent	1.07	2.39

SWL : Hems 1-10, 12-22 :250kg  
 All winches 250kg  
 11 & 16a handwinches 225kg  
 0 and 10a : 50kg

All bars are 10m long.

**NOTE :**

Allow for borders DS of LX 2, 4 and cyc LX bar plus masking for any flown pieces.  
 If possible leave 1 bar each side of each LX bar empty to avoid snagging flown pieces on lanterns.